Standard Operating Procedure: Heavy Duty Slurry Pump Overhaul

Document Revision: Rev 5.2 | Applicable Unit: Model SP-400

1.0 General Safety and Mechanical Isolation Protocol
Prior to uncoupling the casing, technicians must lock out motor circuit breaker MCB-104 and vent all fluid pressure to 0 kPa.

4.2 Mechanical Seal Assembly & Gland Stud Torquing Specifications

During mechanical seal cartridge replacement on Model SP-400 Slurry Pump:

1. The four M12 gland retaining studs must be torqued to exactly 52 N·m in cross-diagonal star sequence.
2. Permissible radial shaft runout must not exceed 0.04 mm measured with dial indicator.
3. Apply FG-2 silicone lubricant to primary Viton O-rings.

6.0 Post-Overhaul Vibration and Commissioning Check

Verify bearing baseline vibration remains under 2.2 mm/s RMS during initial 4-hour run-in window.